

FASTLIFT LEVER BLOCKS - MK I

These blocks have been tried and tested in the tough ship-building industry, and are **heavy duty** units able to cope with hard South African conditions. They are manufactured to ISO 9002 certified quality system standards.

FEATURES INCLUDE:

- Forged steel welded hook casings in place of cast casings.
- Fast free-wheeling system, ensuring minimum operating time.
- Forged steel, heat treated load sheaves for longer service and high fatigue resistance.
- Fail-safe mechanisms to prevent loads from slipping or falling.



SPECIFICATIONS

Model	Capacity (ton)	Load chain falls	Levering effort (kg)	Drawn-up height (mm)	Weight c/w 3m pull (kg)
MINIPULL DLS - 50	0,75	1	16	330	8
81015	1,5	1	21	370	11
81030	3	1	34	450	18
81060	6	2	36	580	30